Constructing lines, &c., for the Imperial Service Troops at Bangalore.

No.	Items of work.	Per.	Quantity.
1	Earthwork	C. yd.	14,539
2	Stone in clay	C. ft.	4,43,902
3	Raw brick in clay	,,	7,992
4	Brick in clay	,,	5,69,348
5	Stone pillars	S. ft.	15,935
6	Clay work	C. ft.	5,868·00
7	Honne-wood work	,,	9,906·98
8	Roofing with Mangalore tiles, with teak reepers	Sqr.	4,700·57
9	Ventilating tiles	Each	2,220
10	Stone slabs 6″	S. ft.	37,662
11	Honne-wood doors for buildings	,,	49,396
12	Do for backyard	,,	8,624
13	Wooden pulleys, complete	L. S.	Rs. 10
14	Honne-wood windows with iron bars, &c.	S. ft.	11,946
15	Mud plastering	Sqr.	8,936·86
16	Pointing with chunam	Sqr.	4,097·41
17	Color washing	,,	9,546·77
18	White washing	R. ft.	33,523
19	Coping with brick in clay and chunam plaster	C. yd.	3,358
20	Earth filling	Sqr.	3,334·12
21	Gravel flooring	,,	197·12
22	Asphalting ½″ thick over 3″ concrete floor	R. ft.	19,578
23	V- shaped drain	L. S.	Rs. 3,581
24	Cast of end walls	S. yd.	1,304
25	Turfing	Sqr.	4,817·14
26	Chunam plastering	C. ft.	5,925
27	Stone staining	Sqrs.	68·55
28	Flooring with cement and plaster	C. ft.	1,68,300
29	Brick in chunam	L. S.	Rs. 60
30	Masonry platform	Sqrs.	80·66
31	Painting 2 coats	,,	239·00
32	Wood oiling	C. ft.	21,238
33	Stone in chunam filling foundation	S. ft.	17,752
34	Flooring stone slabs 3″ thick	C. ft.	1,408·00
35	Teak-wood work	S. ft.	1,008
36	Do doors	,,	1,120
37	Windows	,,	714
38	Ventilators	R. ft.	4,736
39	Ornamental eave boards	L. S.	Rs. 345
40	Rock stand for arms	,,	,, 2
41	Head over backyard, door No. I	R. ft.	,, 296
42	Open box drain	Sqrs.	31·20
43	Asphalte pointing	,,	94·60
44	Tarring	Each	8
45	Cistern	C. ft.	729
46	Brick in chunam, archwork	R. ft.	54
47	Cornice	L. S.	Rs. 50
48	Teak wood doors with copper sheets	,,	,, 400
49	Lightning conductor	Each	,, 5
50	Stone benches	L. S.	,, 10
51	Sundry charges	,,	,, 2,500
52	Roads and enclosure railings	,,	,, 1,000
53	Blasting rock	,,	,, 2,000
54	Roads for lines	,,	,, 2,000
55	V- shaped drains for roads	,,	,, 6,000
56	Hospital room	,,	,, 100
57	Baling water	Each	4
58	Iron rails		

Y. SRINIVASA RAO, *Executive Engr.*

CHITALDRUG DIVISION.

Notice, dated 3rd October 1896.

Notice is hereby given that a sum of Rs. 110-0-2 withdrawn from the Chitaldrug Government Savings Bank stands due in the deposit amount of this office to one task-work contractor Gopal Singh, and that if neither he nor his representative, if any, prefers his claim to the said amount within three months from this date the amount will be paid to his partner Hindoji, who has applied for the same.

K. PRAHLADA RAO, *Offg. Executive Engineer.*